



CROSSRIVERRAIL
DELIVERY AUTHORITY


Cross River Rail Project and Controls Integration



Agenda

Cross River Rail

- our Project
- our Progress
- our Project Controls approach





Cross River Rail



10.2 km
new rail line



5.9 km twin tunnels
under the Brisbane
River and CBD



4 new underground
stations



8 rebuilt
stations




3 new Gold
Coast stations



1 new world class
signalling system



 Cross River Rail
 Existing Rail



Cross River Rail as a solution

- Shorter journey times door to door
- Capacity to increase train frequencies as population grows
- Second river crossing, reducing network frailty
- New stations in more convenient locations
- Integration with new roads & new bus services
- Will make public transport more popular

A catalyst for wider rail transformation

- Current QR rail network map



- Released 2 August 2022



- Future rail network map



Supporting our economy




7,700 jobs in total
(current workforce - 2,700)



More than 1700
subcontractors and
suppliers have already
benefitted

\$3.3m Per day



\$100m Per month





Also delivering...



450

Apprentice/Trainees
over the life of the
project

Currently at

343

apprentice/trainees



614,000

apprentice hours
planned over the life
of the project

Currently at

598,000

hours

Four major works packages

Tunnel, Stations & Development: *Pulse*




Rail, Integration & Systems: *Unity Alliance*



European Train Control System *Sequence Alliance*



New Gold Coast Stations



Some site by site highlights



Mayne Yard North



Mayne Yard North



New crew facility

Exhibition

This document is the property of the Cross River Rail Delivery Authority. It may not be copied or reproduced.



Old station now fully demolished, OHLE installation underway




Victoria Park Feeder station progressing

Twin Tunnels complete

This document is the property of the Cross River Rail Delivery Authority. It may not be copied or reproduced.



Tunnels emerge from Northern Portal



Tracks laid between Albert Street and Woolloongabba

Northern Portal



Northern Portal decline and roof




FRP and concrete works ongoing beneath portal roof

Roma Street

This document is the property of the Cross River Rail Delivery Authority. It may not be copied or reproduced.



Services building reached ground level




Station building works ongoing




Cavern lining works continue

Albert Street

This document is the property of the Cross River Rail Delivery Authority. It may not be copied or reproduced.



Station entry building construction ongoing



Permanent cavern lining continues

Woolloongabba

This document is the property of the Cross River Rail Delivery Authority. It may not be copied or reproduced.



South Cavern mezzanine installation complete



Services building construction ongoing

Boggo Road



Mezzanine installation commenced



Steel and concreting works ongoing

Southern Portal

This document is the property of the Cross River Rail Delivery Authority. It may not be copied or reproduced.



Southern portal dive structure fully excavated



Piling for new Boggo Road bridge underway

Yeronga, Fairfield and Rocklea


This document is the property of the Cross River Rail Delivery Authority. It may not be copied or reproduced.



Yeronga Station



Fairfield Station



Rocklea station – track lowering

New Gold Coast Stations



Hope Island Station, off Hope Island Road



Merrimac Station, off Gooding Drive



Pimpama early works

Signalling system


Queensland Rail Delivery Authority may not be copied or reproduced.




Our Project Controls approach

Delivering within a complex Government Framework

Required to meet Queensland Government Legislation





Required to align with Key Queensland Government Frameworks



Required to Deliver Complex Requirements



Tailoring foundational standards to manage work



Business Case objectives are the core driver of primary project requirements

- Provide the reward and benefits to the project
- Enable greater integration of the project with other projects
- Bring jobs closer to home so more people can access the benefits of what they work
- Manage congestion and reduce greenhouse gases by getting more people onto public transport
- Enable more than \$1 billion in economic benefits for SEQ
- 2X The visibility across the rail network and through the CBD from the south
- Improve school bus times and reduce traffic each year during construction
- Take up road space for construction activities, including faster speeds and shorter times
- Support our contribution to key areas of the greater area such as transportation and smart cities
- Provide quality to connect the CBD to the south via Central, Western and Eastern
- Take up road space for construction activities, including faster speeds and shorter times

SPONSOR REQUIREMENTS

PROGRAM REQUIREMENTS


Structured approach to Risk Appetite helps isolate key Strategic Risks

Strategic Risks:

Risk Appetite:

STRATEGIC RISKS



OPERATIONAL RISKS




Governance:

- Portfolio level – Reviewed Quarterly
- Program level – Reviewed Monthly

On a routine and repeatable basis



Resulting in an Integrated Outcomes/Requirements Framework



The State Infrastructure Plan (SIP) includes a framework to plan and prioritise infrastructure investment and delivery.

Breaking down key objectives into deliverable requirements:



Business Case Objectives

| | |
|---|---|
|  | Provide turn-up-and-go rail services in the inner city |
|  | Enable greater integration of bus and rail services |
|  | Bring jobs closer to home so more people live within 30 minutes of where they work |
|  | Manage congestion and reduce greenhouse gasses by shifting more people onto public transport |
|  | Create more than \$7 billion in direct transport and wider economic benefits for SEQ |
|  | The capacity across the Brisbane River and through the CBD from the south |
|  | Generate about 1500 direct and indirect jobs each year during construction |
|  | Free up road space for commercial vehicles, enabling faster speeds and quicker trips |
|  | Support urban revitalisation in key inner city growth areas such as Woolloongabba and Bowen Hills |
|  | Provide capacity to connect new cities and regional centres to the CBD by rail such as Caloundra, Flagstone and Coomera |
|  | Take rail into new parts of Brisbane's city centre with the first new CBD station in more than 100 years |

Sponsor Requirements

| | |
|------|---|
| SR1 | CRR will deliver an increase of approximately 50% in network capacity, which is additional capacity of about 18,000 rail passenger journeys per day. This will be the key catalyst for transforming the south-east Queensland rail network into a modern digital railway as part of the single integrated transport network accessible to everyone. |
| SR2 | CRR will improve customer experience by reducing journey times and improving frequency by rail through the corridor and to/from Brisbane city. |
| SR3 | CRR will change sectorisation of the rail network by connecting all southern services on the Gold Coast line through a new core section through the city to the North Coast and Redcliffe Peninsula lines. |
| SR4 | CRR will feature new tunnel infrastructure to four underground inner-city stations at Boggo Road, Woolloongabba, Albert Street and Roma Street. It will also include redevelopment of Exhibition station and Dutton Park station. |
| SR5 | CRR will provide world class passenger facing rail safety measures such as platform screen doors at all new underground stations. |
| SR6 | The core section of CRR will achieve a safe, efficient and reliable operational capacity of ultimately 24 TPH in both directions (with service plans aligned with demand). |
| SR7 | CRR will be capable of operating 24 hours a day on special occasions, but will more generally operate 22 hours per day for two days per week (Friday and Saturday) and 20 hours per day on other days (Sunday to Thursday) to provide maintenance windows. |
| SR8 | The CRR infrastructure will support long-term social and economic benefits including future introduction of higher capacity (9-car) trains and thus stations need to allow future provision for 9-car length platforms and associated infrastructure to accommodate the increased passenger throughput. |
| SR9 | CRR will accommodate the Next Generation Ticketing systems as stipulated by TMR in consultation with CRR. |
| SR10 | CRR will be supported by track, stabling and station upgrades that improve the efficiency and use of the CRR tunnel. |
| SR11 | CRR will be designed to support operations with the New Generation Rollingstock (NGR) and integrate with Queensland's new signaling technology (ETCS Level 2 with an ATO overlay). |
| SR12 | New CRR stations and infrastructure will provide for all passenger accessibility requirements. |
| SR13 | New CRR stations will integrate into urban design fabric of the CBD precincts, supporting efficient and effective pedestrian movements, and promoting opportunities for modal integration including pedestrians and cyclists. |
| SR14 | CRR will support the continued sharing of rail network between passengers and freight trains with rail freight operators having the same or better levels of access to the network as without the project. |
| SR15 | Coordinator-General conditions |
| SR16 | Stakeholder requirements |



Managing complex works and integration over time




| Task | Start | End |
|---------------------|-----------|-----------------|
| Configure System | 26-Apr-18 | Configure Phase |
| Configure Assembly | 26-Apr-18 | Mid Config |
| Pre Test | 06-Jun-18 | Build Phase |
| Configure Admin | 06-Jun-18 | Build Admin |
| Start Build | 06-Jun-18 | Build Admin |
| Materials | 06-Jun-18 | Build Admin |
| Assembly System | 06-Jun-18 | Build Admin |
| Assembly Hardware | 06-Jun-18 | Build Admin |
| Mid Build | 06-Jun-18 | Build Admin |
| Quality Test | 06-Jun-18 | Build Admin |
| Electrical Test | 06-Jun-18 | Build Admin |
| System Test | 06-Jun-18 | Build Admin |
| Commission | 06-Jun-18 | Build Admin |
| Job M1PROJ Finished | 06-Jun-18 | Build Admin |

Text Attachment - MPROJ2010
MPROJ2015 - Assembly must complete on time to prevent delay in system configuration.




Managing a complex budget for key stakeholders



A Staged Approach to Risk Management



Leading the uptake of digital project management




Integrating traditional methods with new innovations

CRR Integrated CIMs Schedule (ICIM) by WBS - May 2020 Monthly Report

Commercial in Confidence - Not for Distribution or Copy

Date: 31-May-20
Page: 1 of 3

| Activity | Start | End | Status |
|-----------------------|----------|----------|-------------|
| Part A: Sub-structure | 17/04/20 | 17/04/20 | Completed |
| Part B: Piling | 17/04/20 | 17/04/20 | In Progress |
| Part C: BTCC | 17/04/20 | 17/04/20 | Planned |



Schedule

Quantities

Geometry

REPORTING

Locality: Roma Street

| Station | Boggo Road | | |
|-------------------------------------|-----------------------------|-------|-------|
| CRR Shared Parameters: CRR_CATEGORY | VOLUME (m³) TOTAL | | |
| BEAM | Concrete beam systems | 389 | 26 |
| COLUMN | Concrete Column Systems | 94 | 29 |
| SLAB | In situ reinforced concrete | 3,475 | 85 |
| WALL | Masonry wall systems | 8 | 4 |
| WALL | Reinforced concrete wall | 3,699 | 1,438 |

Status (groups):
 Future Works
 Installed
 WIP

9,439 VOLUME (m³)

4,576 TOTAL

| | |
|-----------|-------------|
| 4,544 | 16.1% |
| Installed | % Installed |
| 100 | 0.4% |
| WIP | % WIP |
| 0 | 0.0% |
| Planned | % Planned |

Donut chart showing volume distribution by category:

- SLAB 3475.445 (36.82%)
- FOUNDATION 1450.1879... (15.36%)
- WALL 3940.2290... (41.74%)
- BEAM 414.6850... (4.39%)

10D VOLUME (m³) by CRR CATEGORY

| Category | Volume (m³) |
|---------------|-------------|
| WALL | ~10K |
| SLAB | ~8K |
| CELLULAR UNIT | ~5K |
| FOUNDATION | ~2K |
| BEAM | ~2K |
| COLUMN | ~1K |
| CORBEL | ~0K |
| ANCHOR | ~0K |
| FRAMING | ~0K |

Integrating trusted methods with new





CROSSRIVERRAIL
DELIVERY AUTHORITY

Cross River Rail