

October 4-6, 2022, Nationals Park, Washington DC



Prevention, Dissension, and  
Extension:  
*A Case Study of the Project Control  
Life Cycle – Schedule through Dispute Resolution*

Aegis Project Controls  
Michael Bograd, PSP  
Russell Wodiska, MBA, EVP



(W) [www.projectcontrolexpo.com/usa](http://www.projectcontrolexpo.com/usa)  
(M) +44 (0) 203 883 1386  
(E) [usa@projectcontrolexpo.com](mailto:usa@projectcontrolexpo.com)

2022

# Speakers



**Russell Wodiska, MBA, EVP**  
President of Dispute Resolution

- 13+ years in Dispute Resolution
- Testifying Expert
- Specialist in Delay, LoP, and Damages



**Michael Bograd, PSP**  
Vice President of Planning & Scheduling

- 16+ years in Project Controls
- Expert in Mega Projects
- Specialist in Data Centers

# Objectives

1

Demonstrate Proper Planning and Scheduling

2

Effective Dispute Resolution

3


Managing Outcomes based on Analysis

# Project Summary

- Project: 3.8M SF distribution center
- General Contractor: RC Andersen
- Owner: Amazon
- Summary:
  - Rock pier foundation with slab on grade
  - Five-story steel and bar-joist warehouse with slab on metal decks
  - Five one-story steel bump outs
  - Precast on the lower levels and metal panel siding on the upper levels
  - The five bump outs include: a main office, three different loading docks, and a mixed-use area (containing the main distribution frame (MDF) room, the demarcation room, and the maintenance area)



# Key Dates



- Amazon required Early Access to red flagged areas
- Would assess liquidated damages against each of the milestones




### MILESTONE DATE ANALYSIS - EXPEDITE ENTIRE PROJECT

Legend:

- Construction work aligns with requested early access date
- Construction work is marginally different than the requested early access date
- Construction work does not complete before the early access date



Task Name	Early Access Date	Weeks Prior to First Receive	Slab Beneath	Slab on Level Above Complete	Roof Above Complete	Ext Walls (Adj)	MEP Complete	AR Fence Complete	All Tasks Complete relative to Early Access Request (weeks)
First Receive	9/12/2021	0							
Area 1: (Level 1)	2/1/2021	-32	11/10/2020	12/16/2020	11/10/2020	12/11/2020	2/10/2021		1
Area 2: Routing Sorter Platform (Level 1.5)	2/8/2021	-31	1/20/2021	2/12/2021	1/5/2021	1/15/2021	2/3/2021		1
Area 3: (Level 1)	2/22/2021	-29	12/28/2020	2/25/2021	1/5/2021	4/21/2021	4/14/2021		8
Area 3: AFE Platform North (Level 1.5)	2/22/2021	-29	12/28/2020	12/16/2020	11/10/2020	2/25/2021	1/12/2021		0
MHE Shaft D	3/1/2021	-28	11/10/2020	11/17/2020	11/10/2020	10/27/2020	2/4/2021		-4
Area 4: (Level 1)	3/8/2021	-27	12/21/2020	3/31/2021	2/9/2021	3/12/2021	5/6/2021		8
Area 4: North SLAM (Level 1.5)	3/8/2021	-27	12/21/2020	1/21/2021	11/10/2020	2/25/2021	1/6/2021		-2
Demarc Construction Complete	3/8/2021	-27	11/16/2020		3/31/2021	2/25/2021	2/17/2021		3
MDF Construction Complete	3/22/2021	-25	11/16/2020		3/31/2021	2/25/2021	3/22/2021		1
MHE Shaft A	3/22/2021	-25	1/25/2021	1/12/2021	11/10/2020	3/3/2021	3/3/2021		-3
Area 5: (Level 1)	3/29/2021	-24	11/16/2020	2/12/2021	1/5/2021	4/21/2021	4/14/2021		3
Area 5: Bump D	3/29/2021	-24	11/16/2020		3/31/2021	2/25/2021	5/25/2021		8
Area 5: AFE South (Level 1.5)	3/29/2021	-24	3/1/2021	2/12/2021	1/5/2021	4/21/2021	3/15/2021		3
Area 5: Shipping Sorter Platform (Level 1.5)	3/29/2021	-24	2/18/2021	4/26/2021	3/15/2021	4/21/2021	3/4/2021		4
Area 6: (Level 1)	4/26/2021	-20	12/24/2020	4/9/2021	3/15/2021	5/6/2021	6/16/2021		7
Area 6: South Slam (Level 1.5)	4/26/2021	-20	3/24/2021	2/12/2021	1/5/2021	4/21/2021	4/7/2021		-1
Area 6: AR Sortation Mezz (Level 1.5)	4/26/2021	-20	4/9/2021	4/26/2021	3/15/2021	5/6/2021	6/28/2021		9
Area 6: Bump A	4/26/2021	-20	1/7/2021		5/21/2021	4/21/2021	7/19/2021		12
MHE Shaft B and C	5/3/2021	-19	10/13/2020	1/12/2021	1/5/2021	1/15/2021	3/3/2021		-9
Bump C	5/10/2021	-18	12/3/2020		4/15/2021	3/12/2021	6/10/2021		4
Bump B	5/24/2021	-16	12/31/2020		6/8/2021	5/6/2021	8/3/2021		10
Area 7: Office Block, Remote Break Rooms (Level 1)	7/19/2021	-8	1/25/2021		1/28/2021	12/11/2020	6/9/2021		-6
Area A: RSP Level 5 - East	4/26/2021	-20	1/12/2021		1/5/2021	12/23/2020	8/3/2021	3/9/2021	14
Area B: RSP Level 4 - East	5/3/2021	-19	1/12/2021	1/12/2021	1/5/2021	1/15/2021	4/14/2021	4/14/2021	-3
Area C: RSP Level 5 - West	5/10/2021	-18	3/16/2021		3/15/2021	3/3/2021	5/10/2021	5/10/2021	0
Area D: RSP Level 4 - West	5/17/2021	-17	4/13/2021	3/16/2021	3/15/2021	3/23/2021	5/17/2021	5/14/2021	0
Area E: RSP Level 3 - East	5/24/2021	-16	3/3/2021	2/17/2021	1/5/2021	1/22/2021	4/28/2021	4/28/2021	-4
Area F: RSP Level 2 - East	5/31/2021	-15	2/12/2021	3/3/2021	1/5/2021	1/15/2021	4/7/2021	4/7/2021	-8
Area G: RSP Level 3 - West	6/7/2021	-14	4/15/2021	4/13/2021	3/15/2021	5/14/2021	6/7/2021	6/7/2021	0
Area H: RSP Level 2 - West	6/14/2021	-13	4/26/2021	4/15/2021	3/15/2021	5/6/2021	6/10/2021	6/14/2021	0

\*Some Level 1.5 "slabs" are checker plate steel or resin deck. Date provided for slab completion is equivalent to steel completion date for those areas.





# Schedule Development

- Worked with key trades to capture the scope and create a low-risk construction sequence



# Schedule Development

- Worked with key trades to capture the scope and create a low-risk construction sequence






# Schedule Development


- Validated the critical path

Project Warrior - BLD4 - Update # 01 - 08.01.2020				04_Longest Path														
Activity ID	Activity Name	Original Duration	Remaining Duration	Start	Finish	Total Float	2020											
							May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	
DIV05-1030	FABRICATE & DELIVER STEEL - NORTHEAST QUADRANT	40	20	26-Jun-20 A	28-Aug-20	-1												
SSTL-NE-2040	ERECT STEEL - COL & L5 - SEQUENCE 1	4	4	31-Aug-20	03-Sep-20	-1												
SSTL-NE-2050	ERECT STEEL - RF - SEQUENCE 1	3	3	04-Sep-20	09-Sep-20	-1												
SSTL-NE-2250	DECK & DETAIL STEEL - L5 - SEQUENCE 1	2	2	10-Sep-20	11-Sep-20	-1												
SSTL-NE-2060	DECK & DETAIL STEEL - RF - SEQUENCE 1	2	2	11-Sep-20	14-Sep-20	-1												
SSTL-NE-2070	ERECT STEEL - L4 - SEQUENCE 1	3	3	15-Sep-20	17-Sep-20	-1												
SSTL-NE-2080	ERECT STEEL - L3 - SEQUENCE 1	2	2	18-Sep-20	21-Sep-20	-1												
SSTL-NE-2090	ERECT STEEL - L2 - SEQUENCE 1	2	2	22-Sep-20	23-Sep-20	-1												
SSTL-NE-2120	ERECT STEEL - L4 - SEQUENCE 2	3	3	24-Sep-20	28-Sep-20	-1												
SSTL-NE-2130	ERECT STEEL - L3 - SEQUENCE 2	2	2	29-Sep-20	30-Sep-20	-1												
SSTL-NE-2140	ERECT STEEL - L2 - SEQUENCE 2	2	2	01-Oct-20	02-Oct-20	-1												
SSTL-NW-2070	ERECT STEEL - L4 - SEQUENCE 9	2	2	05-Oct-20	06-Oct-20	-1												
SSTL-NW-2080	ERECT STEEL - L3 - SEQUENCE 9	2	2	07-Oct-20	08-Oct-20	-1												
SSTL-NW-2090	ERECT STEEL - L2 - SEQUENCE 9	1	1	09-Oct-20	09-Oct-20	-1												
SSTL-NW-2150	ERECT STEEL - MEZZ - SEQUENCE 9	1	1	12-Oct-20	12-Oct-20	-1												
SSTL-NE-2170	ERECT STEEL - L4 - SEQUENCE 3	2	2	13-Oct-20	14-Oct-20	-1												
SSTL-NE-2180	ERECT STEEL - L3 - SEQUENCE 3	2	2	15-Oct-20	16-Oct-20	-1												
SSTL-NE-2190	ERECT STEEL - L2 - SEQUENCE 3	2	2	19-Oct-20	20-Oct-20	-1												
SSTL-NE-2220	ERECT STEEL - L4 - SEQUENCE 4	3	3	21-Oct-20	23-Oct-20	-1												
SSTL-NE-2230	ERECT STEEL - L3 - SEQUENCE 4	2	2	26-Oct-20	27-Oct-20	-1												
SSTL-NE-2240	ERECT STEEL - L2 - SEQUENCE 4	2	2	28-Oct-20	29-Oct-20	-1												
SSTL-NW-2120	ERECT STEEL - L4 - SEQUENCE 10	2	2	30-Oct-20	02-Nov-20	-1												
SSTL-NW-2130	ERECT STEEL - L3 - SEQUENCE 10	2	2	03-Nov-20	04-Nov-20	-1												
SSTL-NW-2140	ERECT STEEL - L2 - SEQUENCE 10	2	2	05-Nov-20	06-Nov-20	-1												
SSTL-NW-2160	ERECT STEEL - MEZZ - SEQUENCE 10	2	2	09-Nov-20	10-Nov-20	-1												
SSTL-SE-2070	ERECT STEEL - L4 - SEQUENCE 5	3	3	11-Nov-20	13-Nov-20	-1												
SSTL-SE-2080	ERECT STEEL - L3 - SEQUENCE 5	2	2	16-Nov-20	17-Nov-20	-1												
SSTL-SE-2090	ERECT STEEL - L2 - SEQUENCE 5	2	2	18-Nov-20	19-Nov-20	-1												
SSTL-SE-2120	ERECT STEEL - L4 - SEQUENCE 6	2	2	20-Nov-20	23-Nov-20	-1												
SSTL-SE-2130	ERECT STEEL - L3 - SEQUENCE 6	2	2	24-Nov-20	25-Nov-20	-1												
SSTL-SE-2140	ERECT STEEL - L2 - SEQUENCE 6	2	2	30-Nov-20	01-Dec-20	-1												
SSTL-SW-2070	ERECT STEEL - L4 - SEQUENCE 15	2	2	02-Dec-20	03-Dec-20	-1												
SSTL-SW-2080	ERECT STEEL - L3 - SEQUENCE 15	1	1	04-Dec-20	04-Dec-20	-1												
SSTL-SW-2090	ERECT STEEL - L2 - SEQUENCE 15	1	1	07-Dec-20	07-Dec-20	-1												
SSTL-SW-2150	ERECT STEEL - MEZZ - SEQUENCE 15	1	1	08-Dec-20	08-Dec-20	-1												
SSTL-SE-2170	ERECT STEEL - L4 - SEQUENCE 7	3	3	09-Dec-20	11-Dec-20	-1												
SSTL-SE-2180	ERECT STEEL - L3 - SEQUENCE 7	2	2	14-Dec-20	15-Dec-20	-1												
SSTL-SE-2190	ERECT STEEL - L2 - SEQUENCE 7	2	2	16-Dec-20	17-Dec-20	-1												
SSTL-SE-2220	ERECT STEEL - L4 - SEQUENCE 8	2	2	18-Dec-20	21-Dec-20	-1												
SSTL-SE-2230	ERECT STEEL - L3 - SEQUENCE 8	2	2	22-Dec-20	23-Dec-20	-1												
SSTL-SE-2240	ERECT STEEL - L2 - SEQUENCE 8	2	2	24-Dec-20	28-Dec-20	-1												



# Schedule Development

- Assigned Resources to all activities



— October Schedule Plan (Piece Count)

— Projections (Based on Average)

— Steel Erected (Piece Count)

## Structural Steel

Current Projected  
Finish Date:  
**May 4, 2021**

Required Daily SS  
Pieces Erected to  
Finish On Time:  
**196**


SS Pieces Erected  
Per Day (Avg):  
**145**

# Risk Management during Schedule Development

**Created** multiple “what if” baselines before determining official plan

**Established** a daily tracker of installation requirements

**Identified** risk factors and mitigation plans as needed (early turnover milestones)



**Developed** production rates with key subcontractors (based on prev. projects)

**Generated** graphic schedules from the outset



# The Main Issue

**Issue:**

Delayed and out-of-sequence steel erection by the steel subcontractor

**Impacts:**

Disrupted numerous follow-on trades (concrete, roofing, loading elevators, fit-out, and building enclosure)

Required the Project to substantially revise the work plan to an extent where the original plan was no longer recognizable


Other trades incurred greater costs by working inefficiently and in a significantly greater number of areas than originally planned

Some trades required different or additional equipment and materials to complete their work (IE: metal panels)

# Methodology

- Aegis performed a disruption analysis by comparing the original Project's plan to the As-Built sequence.
- This methodology demonstrates the disruptive impacts that the steel erection delays and subsequent out-of-sequence installation had on the Project.
- Addresses the discrete cause and effect of the impacts associated with the steel

# Impacts



Required  
Resequencing of  
Work



Additional  
Equipment




Labor Inefficiencies




Additional  
Protection

# Impacts - Resequencing of Work

## Original Concrete Sequence



## Revised Concrete Sequence



Required Resequencing of Work



Additional Equipment



Labor Inefficiencies




Additional Protection




# Impacts – Resequencing of Work

## Revised Concrete Sequence As-Built Quadrant C Concrete Pours



## Original Concrete Sequence



Required  
Resequencing  
of Work



Additional  
Equipment



Labor  
Inefficiencies




Additional  
Protection






# Impacts – Additional Equipment

Original Steel Sequence



Revised Steel Sequence



Required  
Resequencing  
of Work



Additional  
Equipment



Labor  
Inefficiencies




Additional  
Protection




# Impacts - Additional Equipment

## Revised Steel Sequence



Original Steel Sequence



Required  
Resequencing  
of Work



Additional  
Equipment



Labor  
Inefficiencies




Additional  
Protection



# Impacts – Labor


## As-Planned Fit Sequence

As-Planned Fit-out By Area Stacking



## Revised Concrete Sequence

As-Built Fit-out By Area Stacking



Required Resequencing of Work



Additional Equipment



Labor Inefficiencies



Additional Protection



# Impacts – Labor



Required Resequencing of Work



Additional Equipment




Labor Inefficiencies



Additional Protection

## Revised Concrete Sequence


As-Built Fit-out By Area Stacking



68 activities per day

## As-Planned Fit Sequence

As-Planned Fit-out By Area Stacking



Washington, DC - USA

# Additional Protection



Required  
Resequencing  
of Work



Additional  
Equipment



Labor  
Inefficiencies



Additional  
Protection

# Cause and Effect

## Steel Delay Impact

1

Steel delays had a significant impact on the entire project which led to:

- Initial delay to critical path activities
- Revisions to the steel erection sequence due to the use of an alternative steel erection company

## Mitigation Efforts

2

Significant mitigation efforts were undertaken to reduce these delays, these efforts were spread across:

- Concrete work
- Roofing installation
- Elevator install
- Fit-out
- Bump-out installation
- Enclosure + Weathertight

## Material Storage

3

The steel delay also caused the need for both onsite and offsite material storage

# Conclusion

Upfront planning allows for a meaningful dispute resolution analysis

Fair outcome was achieved through stakeholder buy-in of schedule analysis

Steel Completion Delays			
Steel Activity	Planned Finish (UP 01)	Actual Finish (As-Built)	Delay (CD)
Area C - Level 2	11/20/20	02/18/21	-90
Area C - Level 3	11/18/20	02/18/21	-92
Area C - Level 4	11/13/20	02/18/21	-97
Area C - Level 5	10/26/20	02/20/21	-117
Area C - Roof	10/26/20	02/22/21	-119
Area D - Level 2	01/18/21	03/26/21	-67
Area D - Mezzanine	01/13/21	04/12/21	-89
Area D - Level 3	01/14/21	03/26/21	-71
Area D - Level 4	01/11/21	03/26/21	-74
Area D - Level 5	12/17/20	03/26/21	-99
Area D - Roof	12/17/20	04/15/21	-119
Area B - Level 2	02/19/21	04/24/21	-64
Area B - Mezzanine	02/23/21	04/23/21	-59
Area B - Level 3	02/17/21	04/24/21	-66
Area B - Level 4	02/12/21	04/28/21	-75
Area B - Level 5	01/25/21	05/03/21	-98
Area B - Roof	01/25/21	06/08/21	-134
Area A - Level 2	03/24/21	06/07/21	-75
Area A - Mezzanine	03/26/21	05/29/21	-64
Area A - Level 3	03/22/21	05/26/21	-65
Area A - Level 4	03/17/21	06/07/21	-82
Area A - Level 5	02/25/21	06/03/21	-98
Area A - Roof	02/25/21	07/02/21	-127
Main Office	01/21/21	03/10/21	-48
Bump D	03/24/21	04/01/21	-8
Bump C	04/08/21	06/18/21	-71
Bump A	05/14/21	06/22/21	-39
Bump B	06/01/21	06/30/21	-29
<b>Average Delay</b>			<b>-80</b>

# Questions?

**Contact Information:**

*Russell Wodiska*

*Michael Bograd*

*rwodiska@consultaegis.com*

*mbograd@consultaegis.com*

